

Project Budget: MAINTENANCE OF SITE COMMUNICATION MASTS

Generated on 3/1/2026

Structural Ledger

WBS Structure & Description		Qty	UOM	Days	Unit Rate	Allocated Budget	Actual Spent	Variance
1.0	MANPOWER REQUIREMENT & COST BREAKDOWN					NGN 2,420,000.00	—	↗ NGN 2,420,000.00
1.1	Project coordinator	1	EA	10	NGN 40,000.00	NGN 400,000.00	—	↗ NGN 400,000.00
1.2	QHSE supervisor	1	EA	10	NGN 38,000.00	NGN 380,000.00	—	↗ NGN 380,000.00
1.3	Logistics coordinator	1	EA	10	NGN 15,000.00	NGN 150,000.00	—	↗ NGN 150,000.00
1.4	Rigging Team (Lead + Helpers)	5	EA	5	NGN 30,000.00	NGN 750,000.00	—	↗ NGN 750,000.00
1.5	Certified Structural Welder	2	EA	2	NGN 40,000.00	NGN 160,000.00	—	↗ NGN 160,000.00
1.6	Lead Painter & Corrosion Tech	3	EA	4	NGN 40,000.00	NGN 480,000.00	—	↗ NGN 480,000.00
1.7	NDT Technician	1	EA	2	NGN 50,000.00	NGN 100,000.00	—	↗ NGN 100,000.00
2.0	MATERIAL REQUIREMENT & COST BREAKDOWN					NGN 1,145,800.00	—	↗ NGN 1,145,800.00
2.1	Red Oxide Marine Primer (4L Pails)	8	EA	1	NGN 19,500.00	NGN 156,000.00	—	↗ NGN 156,000.00
2.2	Aviation White Gloss Paint (R/W) (4L Pails)	4	EA	1	NGN 19,500.00	NGN 78,000.00	—	↗ NGN 78,000.00
2.3	Aviation Red Gloss Paint (4L Pails)	4	EA	1	NGN 19,500.00	NGN 78,000.00	—	↗ NGN 78,000.00
2.4	Galvanised Steel Bolt/Nut/Washer Sets (M20- M21)	63	EA	1	NGN 2,000.00	NGN 126,000.00	—	↗ NGN 126,000.00
2.5	Low-Hydrogen Welding Electrodes (7018)	1	EA	1	NGN 52,000.00	NGN 52,000.00	—	↗ NGN 52,000.00
2.6	Low-Hydrogen Welding Electrodes (6010)	1	EA	1	NGN 52,000.00	NGN 52,000.00	—	↗ NGN 52,000.00

TOTALS

NGN 8,563,400.00

NGN 0.00

NGN 8,563,400.00

WBS STRUCTURE & DESCRIPTION		QTY	UOM	DAYS	UNIT RATE	ALLOCATED BUDGET	ACTUAL SPENT	VARIANCE
2.7	Industrial Sandpaper (P80/P120 Grit)	20	EA	1	NGN 650.00	NGN 13,000.00	—	↗ NGN 13,000.00
2.8	Toll-rope 16mm x 50m (Certified Rigging Rope)	4	EA	1	NGN 19,500.00	NGN 78,000.00	—	↗ NGN 78,000.00
2.9	NDT Dye Penetrant Test Kits (Cleaner/Pen/Dev)	1	EA	1	NGN 180,000.00	NGN 180,000.00	—	↗ NGN 180,000.00
2.10	Red Oxide Marine Primer (4L Pails)	8	EA	1	NGN 19,500.00	NGN 156,000.00	—	↗ NGN 156,000.00
2.11	Spray gun	1	EA	1	NGN 45,500.00	NGN 45,500.00	—	↗ NGN 45,500.00
2.12	Rags, Detergents, Brushes, hand roller, rubber container	1	EA	1	NGN 124,800.00	NGN 124,800.00	—	↗ NGN 124,800.00
2.13	Abro Thinner (Gallons)	10	EA	1	NGN 650.00	NGN 6,500.00	—	↗ NGN 6,500.00
3.0	TOOLS & EQUIPMENT REQUIREMENT					NGN 1,977,600.00	—	↗ NGN 1,977,600.00
3.1	Conventional Spray Machine	1	RENTAL	10	NGN 19,500.00	NGN 195,000.00	—	↗ NGN 195,000.00
3.2	Inverter Welding Machine	1	EA	10	NGN 25,000.00	NGN 250,000.00	—	↗ NGN 250,000.00
3.3	Industrial Grinding/Cutting Machine	2	EA	10	NGN 13,000.00	NGN 260,000.00	—	↗ NGN 260,000.00
3.4	Erection Pipe Support Sets	2	EA	10	NGN 10,920.00	NGN 218,400.00	—	↗ NGN 218,400.00
3.5	Mechanical Toolbox	1	EA	10	NGN 10,920.00	NGN 109,200.00	—	↗ NGN 109,200.00
3.6	Power-brushing machine	1	EA	10	NGN 19,500.00	NGN 195,000.00	—	↗ NGN 195,000.00
3.7	PPE & Safety Equipment	1	EA	1	NGN 750,000.00	NGN 750,000.00	—	↗ NGN 750,000.00
4.0	INDIRECT COSTS / PRELIMINARIES					NGN 3,020,000.00	—	↗ NGN 3,020,000.00
4.1	Mobilization & Demobilization	1	EA	1	NGN 2,300,000.00	NGN 2,300,000.00	—	↗ NGN 2,300,000.00
TOTALS						NGN 8,563,400.00	NGN 0.00	NGN 8,563,400.00

WBS STRUCTURE & DESCRIPTION		QTY	UOM	DAYS	UNIT RATE	ALLOCATED BUDGET	ACTUAL SPENT	VARIANCE
4.2	Documentation	1	EA	1	NGN 220,000.00	NGN 220,000.00	—	↗ NGN 220,000.00
4.3	Community Fees	1	EA	1	NGN 500,000.00	NGN 500,000.00	—	↗ NGN 500,000.00
TOTALS						NGN 8,563,400.00	NGN 0.00	NGN 8,563,400.00

