



SOLUTION

ENERGY & ENGINEERING SERVICES LTD.

No. 8B Salem Avenue off Aker Road Rumolumeni Port-Harcourt, Rivers State

Tel: +2349153123973, +2349018449467

Email: supplychain@solutionenergylimited.com, info@solutionenergylimited.com, energysolutions.hq@gmail.com

Website: www.solutionenergylimited.com

REF: SEESL/FIPL/26/Q004

DATE: 27/02/2026

COMMERCIAL SUBMISSION FOR COROSION CONTROL FOR GT04 AND GT05 FILTER HOUSING AND TURBINE COMPARTMENT PANELS

A. MATERIAL COST

A1. Steel Sheet Replacement Materials

S/N	Description	Unit	Qty (2 GTs)	Unit Rate (₦)	Amount (₦)
1	5mm Mild Steel Plate	m ²	100	85,000	6,800,000
2	3mm Mild Steel Plate	m ²	250	55,000	8,250,000
3	Welding Electrodes & Consumables	Lot	1	2,500,000	2,500,000
4	Grinding & Cutting Discs	Lot	1	1,200,000	1,200,000
5	Dye Penetrant Kits	Set	10	120,000	1,200,000

Subtotal A1 = ₦19,950,000

A2. Surface Preparation Materials

S/N	Description	Unit	Qty	Unit Rate (₦)	Amount (₦)
1	Abrasive Media (Sand)	Tons	160	95,000	15,200,000
2	Solvents & Degreasers	Liters	900	5,500	4,950,000
3	Cleaning Rags & Waste Materials	Lot	1	900,000	900,000

Subtotal A2 = ₦21,050,000

A3. Painting & Coating Materials (Total 2,772m² for 2 GTs)

S/N	Description	Unit	Qty	Unit Rate (₦)	Amount (₦)
1	Epoxy Primer (Interzinc 52 Part A& B)	Liters	970	25,000	24,250,000
2	Epoxy Intermediate Coat Interguard 475	Liters	90	26,000	23,400,000
3	White Top Coat (Interthane 990 A&B)	Liters	320	25,000	8,000,000
4	Interthane 990 A&B Sky Blue	Liters	420	22,000	9,240,000

We Provide Solutions



SOLUTION

ENERGY & ENGINEERING SERVICES LTD.

No. 8B Salem Avenue off Aker Road Rumolumeni Port-Harcourt, Rivers State

Tel: +2349153123973, +2349018449467

Email: supplychain@solutionenergylimited.com, info@solutionenergylimited.com energysolutions.hq@gmail.com

Website: www.solutionenergylimited.com

5	Interthane 990 Grey/Silver	Liters	100	20,500	2,050,000
6	Thinner GTA 220	Liters	450	4,000	1,800,000

Subtotal A3 = ₦68,740,000

A4. Insulation Rehabilitation Materials

S/N	Description	Unit	Qty	Unit Rate (₦)	Amount (₦)
1	IZOCAM Rockwool Insulation	m ²	260	84,000	21,840,000
2	Wire Mesh (Galvanized)	Rolls	20	106,250	2,125,000
3	Fasteners & Pins	Lot	1	950,000	850,000
4	Aluminum Cladding Sheets	m ²	220	22,000	4,840,000
5	Sealants	Pcs	43	15,500	666,500

Subtotal A4 = ₦30,321,500

TOTAL MATERIAL COST (A)

₦140,061,000

B. TOOLS & EQUIPMENT COST (2 Units)

S/N	Description	Duration	Rate (₦)	Amount (₦)
1	Airless Spray Machines	50 days	120,000/day	6,000,000
2	Abrasive Blasting Machine	40 days	150,000/day	6,000,000
3	Air Compressor	40 days	130,000/day	5,200,000
4	Welding Machines	50 days	50,000/day	2,500,000
5	Scaffolding (Full Enclosure)	2 months	3,500,000/month	8,000,000
6	DFT Gauge & Inspection Tools	Lump Sum	—	3,500,000
7	Air Tank, Spray Gun, Respirators	50 days	150,000/day	7,500,000
8	Safety Equipment (PPE bulk)	Lump Sum	—	4,000,000
9	Tarpaulin (for Inclement Weather)	40 days	6,000	240,000

TOTAL EQUIPMENT COST (B) = ₦42,940,000

We Provide Solutions

No. 8B Salem Avenue off Aker Road Rumolumeni Port-Harcourt, Rivers State

Tel: +2349153123973, +2349018449467

Email: supplychain@solutionenergylimited.com, info@solutionenergylimited.com energysolutions.hq@gmail.com

Website: www.solutionenergylimited.com

C. HUMAN RESOURCE COST (50 Working Days – 2 GTs)

S/N	Personnel	Qty	Daily Rate (₦)	Days	Amount (₦)
1	Project Manager	1	150,000	50	7,500,000
2	Site Supervisor	1	100,000	50	5,000,000
3	QA/QC Inspector	1	120,000	50	6,000,000
4	Safety Officer	1	100,000	50	5,000,000
5	Certified Welders	3	70,000	40	8,400,000
6	Fabricators	2	65,000	40	5,200,000
7	Blasters/Painters	6	60,000	45	16,200,000
8	Insulation Technicians	3	60,000	20	3,600,000
9	Scaffolder/Riggers	5	35,000	50	8,750,000
10	Helpers	3	30,000	50	4,500,000

TOTAL HUMAN RESOURCE COST (C) = ₦70,150,000

D. LOGISTICS & ADMINISTRATION

S/N	Description	Amount (₦)
1	Mobilization & Demobilization	8,000,000
2	Site Accommodation & Welfare	11,500,000
3	Equipment Utilities & Documentation	3,500,000
4	Community	6,500,000
		29,500,000

TOTAL LOGISTICS (D) = ₦29,500,000

SUMMARY OF COST

Category	Amount (₦)
A – Materials	140,061,000
B – Equipment	42,940,000
C – Human Resources	70,150,000
D – Logistics/Admin	29,500,000



SOLUTION

ENERGY & ENGINEERING SERVICES LTD.

No. 8B Salem Avenue off Aker Road Rumolumeni Port-Harcourt, Rivers State

Tel: +2349153123973, +2349018449467

Email: supplychain@solutionenergylimited.com, info@solutionenergylimited.com energysolutions.hq@gmail.com

Website: www.solutionenergylimited.com

TOTAL	282,651,000.00
7.5% VAT	21,198,825.00

GRAND TOTAL PROJECT COST (GT04 & GT05) ₦303,849,825.00

AMOUNT IN WORDS: Three Hundred and Three Million, Eight Hundred and Forty-Nine Thousand, Eight Hundred and Twenty-Five Naira Only.

COMMERCIAL TERMS

- Payment Terms: 40% Advance, 40% Progress, 20% Upon Completion
- Project Duration: 30–50 Working Days
- Validity: 60 Days
- Warranty: 12 Months on workmanship

Basis of Estimate:

- Total Surface Area per GT Unit = 2,772m²
- Two (2) Units: GT04 & GT05
- Coating System: 1 Primer + 2 Epoxy Finish Coats
- Currency: Nigerian Naira (₦)
- Duration: 25 Working Days per Unit
- Pricing based on prevailing Nigerian industrial rates (2026 estimate)

FOR SOLUTION ENERGY & ENGINEERING SERVICES LTD.



MARKETING/SALES DIRECTOR.

We Provide Solutions